Validate	Print	Help	Percentage BoC
----------	-------	------	----------------

Tender Inviting Authority: Staff Officer (civil),CCL, Kathara

Name of Work: Construction of Rain water Harvesting System at Govindpur Project Office and Govindpur Hospital, under Govindpur PH-II OCP, Kathara Area.

	Category of Services (To Be Selected by Department)		To Be Entered by Department		
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER#	TEXT #	NUMBER	NUMBER #	TEXT #
SI. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Item Description/ Heading					
2	Earth work in excv. By mechanical means (Hydraulic excavator)/ Manual means in foundation trenches or drains (not exceeding 1.5m in width or 10sqm on plan) incl. Dressing of sides and ramming of bottom lift lupto1.5m incl. Getting out the excv. soil and disposal of surplus soil as dir.within a lead of 50m all kind of soil.	225.62	m3	206.70	46635.65	INR Forty Six Thousand Six Hundred & Thirty Five and Paise Sixty Five Only
3	Supplying and filling in plinth with Local sand under floors incl. watering , ramming consolidating and dressing complete.	21.44	m3	635.35	13621.90	INR Thirteen Thousand Six Hundred & Twenty One and Paise Ninety Only
4	Providing and laying in position cement concrete of specified grade excluding thecost of centering & shuttering all work up to plinth level 1:3:6 (1 cement : 3 coars sand 6 graded stone agg 20 mm nominal size	27.93	m3	5276.40	147369.85	INR One Lakh Forty Seven Thousand Three Hundred & Sixty Nine and Paise Eighty Five Only
5	Providing and laying in position cement concrete of specified grade excl.the cost of centering and shuttering- All work upto plinth level:1:2:4 (1cement:2coarse sand:4 graded stone agg.20mm nominal size).	61.06	m3	5829.70	355961.48	INR Three Lakh Fifty Five Thousand Nine Hundred & Sixty One and Paise Forty Eight Only
6	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 11.3.1 40 mm thick with 20 mm nominal size stone aggregate	124.20	m2	424.75	52753.95	INR Fifty Two Thousand Seven Hundred & Fifty Three and Paise Ninety Five Only
7	Brick work with FPS bricks of class designation 50 in foundation and plinth in cement mortar 1:6 (1cement :6 coarse sand).	16.58	m3	4482.90	74326.48	INR Seventy Four Thousand Three Hundred & Twenty Six and Paise Forty Eight Only

8	Structural steel work welded in built up sections,trusses and framed work incl. Cutting, hoisting,ixing in position and applying a prining coat of approved steel primer all complete	1167.82	kg	80.30	93775.95	INR Ninety Three Thousand Seven Hundred & Seventy Five and Paise Ninety Five Only
9	Boring/drilling bore well of required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/ bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge, upto 90 metre depth below ground level. All types of soil. 300 mm dia	80.00	mtr	415.60	33248.00	INR Thirty Three Thousand Two Hundred & Forty Eight Only
10	Supplying, assembling, lowering and fixing in vertical position in bore well unplasticized PVC medium well screen (RMS) pipes with ribs, conforming to IS: 12818, including hire & labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer-in-charge. 200 mm nominal size dia	40.00	mtr	823.68	32947.20	INR Thirty Two Thousand Nine Hundred & Forty Seven and Paise Twenty Only
11	Supplying, filling, spreading & leveling stone boulders of size range 5 cm to 20 cm, in recharge pit, in the required thickness, for all leads & lifts, all complete as per direction of Engineer-incharge.	12.56	m3	145.50	1827.48	INR One Thousand Eight Hundred & Twenty Seven and Paise Forty Eight Only
12	Supplying, filling, spreading & leveling gravels of size range 5 mm to 10 mm, in the recharge pit, over the existing layer of boulders, in required thickness, for all leads & lifts, all complete as per direction of Engineer-in-charge.	12.56	m3	145.50	1827.48	INR One Thousand Eight Hundred & Twenty Seven and Paise Forty Eight Only
13	Supplying, filling, spreading & leveling coarse sand of size range 1.5 mm to 2 mm in recharge pit, in required thickness over gravel layer, for all leads & lifts, all complete as per direction of Engineer -in-charge.	12.56	m3	145.50	1827.48	INR One Thousand Eight Hundred & Twenty Seven and Paise Forty Eight Only
14	Gravel packing in tubewell construction in accordance with IS: 4097, including providing gravel fine/ medium/ coarse, in required grading & sizes as per actual requirement, all complete as per direction of Engineer-in-charge.	7.54	m3	1219.55	9195.41	INR Nine Thousand One Hundred & Ninety Five and Paise Forty One Only
15	Providing ,hoisting and fixing upto floor five level precast reinforced cement conc. Work in string courses copings bands bed plates, anchor blocks plain window sills and the like incl. The cost of required centering, shutt. Finishing smooth with 6mm thick cement plaster 1:3 (1cement:3fine sand) on exposed surface compl. Upto but excl. Thecost of reinforcement with 1:2:4(1cement:2 coarsesand:4 graded stone agg. 20mm nominal size.	16.98	m3	7134.05	121136.17	INR One Lakh Twenty One Thousand One Hundred & Thirty Six and Paise Seventeen Only
16	Reinforcement for RCC work incl. Straightening, cutting, bending, placing in position and binding all complete upto plinth level .Thermo-Mechanically Treated bars	1358.40	kg	70.69	96025.30	INR Ninety Six Thousand &Twenty Five and Paise Thirty Only
17	Supplying, laying and fixing in horizontal positon unplasticized PVC medium well casing (CM) pipe of required dia confirming ti IS: 12818, including required hire and labour charges, fittings & accessories etc. all complete as per direction of Engineer in charge 150mmm nominal size dia.	84.00	mtr	574.45	48253.80	INR Forty Eight Thousand Two Hundred & Fifty Three and Paise Eighty Only

Quoted Rate in Words			INR Zero Only				
Quoted Rate in Figures			Select		0.00	INR Zero Only	
otal in Figures					1324024.79	Four and Paise Seventy Nine Only	
26	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only	
25	Centring and shuttering including strutting, propping etc. and removal of form work for foundations, footings, bases of columns for mass concrete	331.20	m2	239.95	79471.44	INR Seventy Nine Thousand Four Hundred & Seventy One and Paise Forty Four Only	
24	Carriage of material by mechanical transport incl.loading unloding & stacking earth 1 KM lead	78.94	m3	127.56		INR Ten Thousand &Sixty Nine and Paise Fifty Nine Only	
23	Filling available excv.earth (excl. rock) in trenches,plinth, sides of foundations etc. in layer not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, lead upto 50m and lift upto 1.5m.	10.04	m3	169.79		INR One Thousand Seven Hundred & Four and Paise Sixty Nine Only	
22	Providing and fixing unplasticised PVC pipe clips of approved design to unplasticised PVC rain water pipes by means of required length including cutting brick work and fixing in cement mortar 1:4(1cement:4 coarse sand) and making good the wall etc. complete.110mm	40.00	nos	225.90		INR Nine Thousand &Thirty Six Only	
21	Providing and fixing on wall face upplasticised PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipe confoming to IS: 13592 type A including jointing with seal ring conforming to IS 1382 leaving 10mm gap forthermal expansion. (a)110x110x110mm.	24.00	nos	178.85		INR Four Thousand Two Hundred & Ninety Two and Paise Forty Only	
20	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS: 13592 Type A, including jointing with seal ring conforming to IS: 5382, leaving 10 mm gap for thermal expansion (b)110mm bend.	24.00	nos	111.60	2678.40	INR Two Thousand Six Hundred & Seventy Eight and Paise Forty Only	
19	Providing and fixing on wall face upplasticised Rigid PVC rain water pipe confoming to IS: 13592 type A including jointing with seal ring conforming to IS: 5382 leaving 10mm gap for thermal expansion.single socketed pipes.110mm dimeter.	260.00	mtr	261.35	67951.00	INR Sixty Seven Thousand Nine Hundred & Fifty One Only	
18	12mm cement plasteer finished with a floating coat of neat cement of mix 1:4 (1cement:4 fine sand).	66.45	m2	272.20	18087.69	INR Eighteen Thousand & Eighty Seven and Paise Sixty Nine Only	